


Banner Gateway Medical Center

Gilbert, AZ

Facades 

Project Details

Owner

Banner Health

General Contractor

McCarthy

Architect

SmithGroup

Building Type

Healthcare

Onsite Assembly Date

September 2021

Panel Type

StoPanel® Classic ci,
StoPanel® Metal ci, and
StoPanel® Backup

Project Overview

As part of a massive statewide expansion, Banner Health provided an opportunity to expand on their Gateway Campus, revealing a project fully suited for Sto Panel Technology® prefabricated wall panels. The need for panelization was obvious, and the project team proceeded with an integrated game plan from day one. In order to guarantee the schedule, and provide cost predictability while minimizing the impact on the day to day operations on the campus, StoPanel Systems were an obvious choice for this 106,578 sqft medical center.

Job Requirements

Given the need to utilize the schedule to its fullest potential, and not impact ongoing operations at the campus, a prefabricated approach was absolutely necessary. By combining all finishes in the factory to provide a fully assembled envelope, this project was able to optimize the prefabrication process while delivering the upmost quality and aesthetic appeal.

Smart Solution

MKB Construction delivered a wide variety of StoPanel systems, StoPanel Classic ci, StoPanel Metal ci, and StoPanel Back-up with a masonry veneer cladding to achieve a multiple aesthetic facade with our compatibility issues. Composed of just over 400 panels, this project was installed in 4 months time, something that would have taken 3-4 times longer if approached traditionally.



602-256-6172
www.mkbc.com